Dyer Well Drilling and Service, Inc.
7300 Millett Hwy.
Lansing, MI 49301
517-322-0598

10/21/26

Village of Pinckney
Dustin Moma
d.moma@villageofpinckney.org

RE: Proposed cleaning and overhaul of pump in Well 1

Mobilization	
Remove pump and pipe	
Airlift well with compressor	
Clean well with solution (recirculation with tank- five (5) days	
Evaluate pump and piping	
Provide and install: pump bowl, column and suction pipe, bearings, retainers, shaft incl. sleeves and couplers	
Rebuild 40 hp motor, incl. new bearings and refurbishing windings	
Load test 40 hp motor	
Disinfection	
Re-install pump and pipe	
Documentation of pump and motor analysis	
One (1) bacteria sample	
Misc. material	
All labor, incl. crane charge	$70,590

Two (2) non detect bacteriological water samples, twenty four (24) hrs apart will be required to satisfy Type I requirements.
All applicable safety procedures are to be followed by our employees.

Thank you

Michael Dyer