QUOTATION

Village of Pinckney
1598 Patterson Lake Road
Pinckney, MI 48169

QUOTE # DLC 2026-0911-3

Attn: Mr. Mike Hughes

DATE September 11, 2026

REFERENCE **Well No. 1 Conventional Clean and Pump Overhaul (Best Case Scenario)**

Mobilize to site with 2 man crew, support truck, pump hoist rig and cleaning tank. Set up and conventionally in place clean the well for 5 days with the pumping equipment being removed on the fifth day. Once the pump has been successfully removed we will bring to our warehouse facility for teardown and inspection. A report with our findings will be provided.	
Labor, travel, equipment and materials to complete the above tasks	$26,900.00
Pump replacement parts - new wear rings for pump bowl, strainer basket, new bowl and head shaft, sleeves and couplings for shafting, new bowl bearings, stuffing box bearing and consumables.	$11,876.00
Shop and machine labor to machine shafts, assemble pump and stage	$5,460.00
Standard 40 hp recondition - load test, disassemble, clean, dip and bake the windings, replace upper and lower bearings, assemble, test and paint.	$4,206.52
Labor, equipment and travel to mobilize to site, install pumping equipment, test, disinfect the well and coordinate samples with Mike. This assumes we will pull the first sample and Mike will pull the second.	$4,240.00
Note - This proposal is best case scenario and assumes all of the pumping equipment can be reused and repaired. The 40 hp motor is a standard recondition.	
Total:	**$52,682.52**

ACCEPTED BY _____

TITLE _____

DATE _____

PEERLESS-MIDWEST, INC.

DC Coulier

DC Coulier, Project Manager